### **Solar Power Satellite**

- Toward Unexplored Frontier with Nobel Technologies -

Naoki Shinohara Professor, Kyoto University, Japan

# <u>Solar Power</u> Satellite (SPS)

36,000km Microwave Power Transmission

Energy Availability Factor Ground PV

: < 15% (Night, Rain...)

Space PV (SPS)

: >90% (No Night in 36,000km Orbit, No Rain by Microwave Propagation)

-> SPS is huge, stable, and CO<sub>2</sub>-less future power station

2-4kmφ Receiving Antenna

# Significance of SPS

Mile Stone toward Future Space Development (Huge Space Satellite (Structure))


### Future Stable Solar Power Station without CO<sub>2</sub> (Huge Solar Power from Satellite)

[Key Technologies for SPS]

- Economical Launch System (Reusable Rocket, OTV, etc.)
  - Totally <10,000 tons Space Segment
- Construction/Maintenance of Huge Space Segment (by Robots)
  - > 2km Structure in space with Solar Cells and WPT
- Power Management in Plasma
  - > 1 Million kW (1GW) Power (> 10-100kV in Plasma)
- Wireless Power Transfer Technology (by Microwave, Laser)
  - 36,000km WPT with > 50% (Electricity -> WPT (>90%)-> Electricity)

### Various SPS Models

First SPS (Glaser, P.E.)




MR-SPS (CAST, China)


SPS-omega (China)

## Scale of Space Structure

\_\_\_\_\_ 10 m \_\_\_\_\_ 100 m \_\_\_\_\_ 1 km \_\_\_\_\_ 10 km \_\_\_\_\_ 100 km



International Space Station




SPS

Modular Reflector






### How to Launch > 10,000 tons Space Segment 2 Step Launch (Ground $\rightarrow$ LEO(400km), LEO $\rightarrow$ GEO(36,000km)



"Mission Image of Japanese SPS", NEDO SSPS Report, 1994

### How to Construct/Maintain > 2km Space Structure

#### by Robot for SPS Construction/Maintenance




Robot in Space



Storage


Image of SPS Structure (Solar Cell, WPT) (Easy Construction)




Unit Structure (Micro : Rigid, Macro : Soft) Actively Fluctuated Structure

Structure Friendly Robot Robot Friendly Structure


#### **Robot on Structure**





NASDA SSPS Report, 2001

#### Test Bed of Automatic Construction of SPS Structure on Ground



# Significance of SPS

Mile Stone toward Future Space Development (Huge Space Satellite (Structure))

### Future Stable Solar Power Station without CO<sub>2</sub> (Huge Solar Power from Satellite)

[Key Technologies for SPS]

- Economical Launch System (Reusable Rocket, OTV, etc.)
  - Totally <10,000 tons Space Segment
- Construction/Maintenance of Huge Space Segment (by Robots)
  - > 2km Structure with Solar Cells and WPT
- Power Management in Plasma
  - > 1 Million kW (1GW) Power (> 10-100kV in Plasma)
- Wireless Power Transfer Technology (by Microwave, Laser)
  - 36,000km WPT with > 50% (Electricity -> WPT (>90%)-> Electricity)


#### Spin Off/In Technology for/from Commercial WPT

#### Proposal of Spin-off / Landing Applications of SPS by JAXA (2017)


• Laser Power Transfer to Flying Drone




• <u>Microwave Power Transfer</u> to Stratospheric Platform (>MW)



• Laser Power Transfer to Driving Rover on Moon



 <u>Radar Rain Gauge</u> with Large Expanded Structure (> 30m)



Beam WPT via Radio Wave in Japan

[R&D Project toward SPS by METI (2017 - 2018)]

• MPT to Flying Drone with Developed (2015) Phased Array

